

INDIANA HARBOR AND CANAL MAINTENANCE DREDGING AND DISPOSAL ACTIVITIES – DESIGN DOCUMENTATION REPORT

RAILROAD RELOCATION

APPENDIX F

U.S. Army Corps of Engineers, Chicago District
Civil Design Section, Design Branch

January 2000

RAILROAD RELOCATION APPENDIX

APPENDIX F

TABLE OF CONTENTS

PURPOSE AND SCOPE	1
GENERAL	1
SITE LAYOUT	1
General.....	1
Railroad Alignment.....	2
Plan/Profile.....	2
PROJECT FEATURES	2
General.....	2
Ballast System and Roadbed.....	3
Design Criteria.....	3
Project Design Specifics	3
Drainage Ditch.....	4
Rail Track System.....	4
Horizontal Curves	4
Grades and Vertical Curves	5
Staging/Storage Areas.....	5
MATERIAL QUANTITIES	5
General.....	5
Quantities Generation.....	5
REAL ESTATE	6
CONSTRUCTION SEQUENCE	6
ATTACHMENT 1	7
Design Criteria	7
ATTACHMENT 2	8
Design Calculation and Assumptions	8
ATTACHMENT 3	38
Local Sponsor's Concurrence with Preliminary Railroad Relocation Design.....	38

LIST OF TABLES AND PLATES

Table F - 1 Railroad Relocation Material Quantities	34
-----------------------------------------------------------	----

Plate F - 1 Typical Cross-sections of Railroad Relocation

Plate F - 2 Plan View of Railroad Relocation

Plate F - 3 Plan and Profile (1 of 4)

Plate F - 4 Plan and Profile (2 of 4)

Plate F - 5 Plan and Profile (3 of 4)

Plate F - 6 Plan and Profile (4 of 4)

Plate F - 7 Cross Sections (1 of 7)

Plate F - 8 Cross Sections (2 of 7)

Plate F - 9 Cross Sections (3 of 7)

Plate F - 10 Cross Sections (4 of 7)
Plate F - 11 Cross Sections (5 of 7)
Plate F - 12 Cross Sections (6 of 7)
Plate F - 13 Cross Sections (7 of 7)
Plate F - 14 Soil Borings
Plate F - 15 Real Estate

PURPOSE AND SCOPE

1. The purpose of this appendix is to present the design criteria, engineering methods and procedures that were used to prepare a detailed railroad relocation and layout for rerouting the CSX side track crossing the ECI property to the northern portion of the property. This includes establishing the horizontal and vertical alignment, profiles and location of the relocated railroad track, calculating construction quantities and defining the real estate requirements.

2. The CSX Transportation Railroad Relocation is being performed as part of the Indiana Harbor and Canal (IHC) and Confined Disposal Facility (CDF) project. The project includes maintenance dredging of the IHC and disposal of the dredged materials in a CDF on the former Energy Cooperative, Inc. (ECI) oil refinery site. The CDF plan includes construction on a portion of the ECI property, which is separated by a 100 feet wide, multiple railroad track ownership/easement corridor. Most of the corridor was abandoned and is presently in use by one lead/side track operated by CSX Transportation. This lead track will be relocated to maximize an optimal dredged sediment placement plan that provides a more economical and constructable CDF design.

GENERAL

3. The project features consist of ballast system and roadbed, adjacent drainage ditches, grading, and slopes required for proper operation of the realigned railway track. The rail track system consists of the track line rails, ties, plates, spikes, anchors, and appurtenant supports. Requirements for implementing this plan include an optimal railway alignment for the relocated track including the curve design as appropriate and required for a single duo rail, side and lead commercial track line to compliment and fit the CDF perimeter, adjacent ditch and groundwater cut-off wall and the extension of the RCRA CAP under the relocated track. The groundwater cut-off wall is required to contain on-site contaminants as well as contaminants from the dredged material. For further information on the groundwater cut-off wall, see Appendix B, "Groundwater Protection". The track design will conform to standard American Railway Engineering Association (AREA) requirements with the first and last 150 to 190 feet of track to be constructed by the railway owners and the track relocation right-of-way (ROW) will not exceed 60 feet. While this appendix provides an overview of the railroad relocation, details regarded the RCRA CAP, the groundwater cut-off wall and utility relocations will be addressed during the preparation of final plans and specification.

SITE LAYOUT

General

4. The site layout design information was developed on a CADD computer system using existing digital topographic and planimetric mapping. All computer work was performed within the Micro-Station software system.

Railroad Alignment

5. Calculations to determine the alignment of the proposed Railroad relocation were done with 100' tangents between reversing curves. Existing data was taken from Micro-Station topographic file. An iterative mathematical solution could have been made by hand but given the number of unknowns, a direct solution yielding a 100' tangent was not possible. Further calculations were made by using a computer spreadsheet and GEOPAK COGO. The relocation alignment in the DDR, with respect to the northeast corner of the CDF, differs from that shown on Figure 24 (page 112) of the CMP. The siding now crosses Indianapolis Blvd at 90 degrees. This realignment was necessary so that the existing railroad crossing at Indianapolis Boulevard could be utilized therefore eliminating the need for resurfacing and an extensive new crossing protection system. The revised alignment was designed to maximize space for the CDF while causing minimal or no impacts to Indianapolis Blvd. Plate F-2 shows the railroad relocation layout.

6. The solution for the alignment for curves 1 and 2 was obtained graphically in Micro-Station by modifying the arc angle of curve 2 so that a 575 radius curve (#1) could meet a #10-turnout, as provided by the railway owners, where the relocation matches back into the existing rail.

7. In order to maximize the amount of space available for the CDF, a trial and error method was used to design curves 3 and 4. The solution that maximizes the area was one that has a 100' tangent between the two 575' (minimum radius) curves 3 and 4. This was obtained using an influence angle, $I_2 = 79.9d$ for curve 4 and an influence angle $I_1 = 51.598d$ for curve 3. The tangent between the curves is 100.118'. See Attachment 2 for all calculations and assumptions.

Plan/Profile

8. After the alignment was inputted, plan and profiles were derived using existing digital topographic and planimetric mapping. The proposed profile was designed so that the railroad sub-base would not be affected by any surface water runoff. The profile was also adjusted to allow for the design and construction of a 3' RCRA CAP underneath the relocated track within the R.R. ROW. Standard F size sheets (40" x 28") were produced with 1" = 50' scale. These were then reduced to plate size drawings (11" x 17"). Plates F-3 to F-6 show the profile with the corresponding plan view. Plates F-7 to F-13 show cross-sections along the profile.

PROJECT FEATURES

General

9. As discussed before, the project features include the ballast system and

roadbed, adjacent drainage ditches, grading, and slopes required for proper operation of the realigned railway track. The rail track system consists of the track line rails, ties, plates, spikes, anchors, and appurtenant supports. In general, the design of the features follows that which was proposed in the Comprehensive Management Plan (CMP) and the CSX Transportation, Guidelines and Specifications for Design and Construction of Commercial Tracks except for minor modifications based on more detailed design analyses. Each feature will be discussed below.

Ballast System and Roadbed

Design Criteria

10. Roadbed width, ditches and slopes shall conform to current CSXT standard roadbed and ballast for industry tracks. This includes 2% subgrade slope, 6" minimum compacted subballast, and 6" minimum ballast at grade point center-line of track. If track is super-elevated then 6" minimum ballast is required below tie under low rail. For cut sections, minimum width of 10' for ditch and 2' for bottom of ditch. Track and ditch gradients may increase ditch size and its distance from centerline of track, and slope can vary as needed for stability from 2:1 in sand to ¼:1 in solid rock. For fill sections, slope as required by fill material (1 ½: 1 maximum) and geotextiles, if used, shall be placed between the top of the subgrade and the bottom of the subballast. Roadbed for commercial trackage within CSXT ROW and parallel to a main or operating track shall be constructed a minimum of 6 inches lower than that of the nearest main or operating track whenever drainage of the existing track can be affected by the new construction.

11. Turnout locations require additional roadbed to support the track structure and to provide proper walkways for CSXT train crews. CSXT requires that the roadbed taper from the existing section 100-feet preceding the point of switch (the point at which a track begins to diverge from another) to 18-feet from the centerline at the point of switch. The 18-foot roadbed is to extend from the point of switch to the transition with the 12-foot roadbed on the diverging track.

Project Design Specifics

12. The designed ballast system consists of a 9 ½ foot wide standard A.R.E.A. size 4-A ballast on a compacted 12" minimum sub-ballast with a 20-foot wide crest and 2H: 1V side slopes in typical cut cross-sections. 4-A ballast is defined as having 100% passing 2½ " screen size, 90-100% passing 2" screen, 60-90% passing 1½ " screen size, 10-35% passing 1" screen size, 0-10% passing ¾ " screen size and 0-3% passing 3/8 " screen size. Geotextiles are not required. In fill cross-sections, the sub-ballast crest widths vary. The crest width allows for a walkway extended from the centerline of the track on both sides. Plate F-1 shows typical cross-sections.

13. The subgrade shall be compacted and finished so that it directs water away from the track. The design slope is 2% from the centerline of the track on both sides. See Attachment 2 for all calculations and assumptions.

Drainage Ditch

14. The drainage system is sized to carry drainage without ponding of water against the roadbed. The ditch is designed to contain the drainage water as it filters into the site as normal. Drainage shall not be diverted, directed toward CSXT, or increased in quantity without prior approval and agreement with CSXT. Track roadbeds fills shall not be used as dams or levees for retention of water nor shall CSXT ROW be utilized for retention or settling basin.

15. The designed side slopes of the drainage ditch are 3H:1V with a 2-foot depth and 3-foot bottom width for constructability (Plate F-1). The profile was also raised so that the entire typical section is above the existing ground line.

Rail Track System

16. The rail track system consists of the track line rails, ties, plates, spikes, anchors, and appurtenant supports. The controlling elevation was the existing track elevations at the west and east ends of the project site. Curve information for each curve includes the intersection angle, degree of curve, radius, tangent distance, external and length of curve. Plate F-1 shows cross-sections of the rail track system.

Horizontal Curves

17. Trackage was designed using the minimum degree (maximum radius) of curve practicable. It is typical to use the chord definition of the degree of curve, which is defined as the central angle subtended by a 100 foot chord. It is denoted by D_c , where $\sin \frac{1}{2} D_c = 50/R$. Wherever practicable, a curve should begin beyond the last switch tie, but if required by special circumstances, a curve may extend onto the switch ties. In no case shall a curve begin between the point of switch and the heel of frog (the end of the point at which two running rails intersect within a turnout or crossing that is furthest from the point of switch).

18. A curve should be avoided at the loading point of a bulk loading facility or at an under track unloading structure. Spiral curves and super-elevations are not normally required, but, if required by special circumstances, shall be designed according to current CSXT standards. Tangents (straight sections), as specified in Attachment 1 - Design Criteria, shall separate reverse curves (curves following each other in opposite directions).

19. The designed curves met the above criteria. As stated earlier, the designed alignment for curves 1 and 2 was obtained by modifying the arc angle of curve 2 so that a 575 radius curve (#1) could meet the #10-turnout. The design for curves 3 and 4 was one that has a 100.118' tangent between the two 575' (minimum radius) curves 3 and 4. Additional information is provided on plate F-2. See Attachment 2 for all calculations and assumptions.

Grades and Vertical Curves

20. Track grades are to the minimum possible, consistent with terrain requirements. Grades were carefully designed to ensure that motive power available will handle the tonnage to be moved. This takes into consideration number of cars, whether loaded or empty, etc. Grades for “Load / Unload in Motion” trackage were designed so that a train is under power with no bunching of couplers while loading or unloading.

21. Frequent changes of grade were avoided. Vertical curves were provided at all grade changes, and were as long as practicable. Minimum standards for calculation of vertical curves are specified in Attachment 1, Design Criteria. Neither grade changes nor vertical curves are within the limits of switch ties. The designed curve information is provided on plate F-2. See Attachment 2 for all calculations and assumptions.

Staging/Storage Areas

22. Staging/storage areas are provided within the existing CSXT ROW as shown on plate F-2. Details will be finalized during the preparation of plans and specifications.

MATERIAL QUANTITIES

General

23. Quantities were either manually calculated or computer calculated using the InRoads or MicroStation software. They consist of track complete in place, ballast, sub-ballast, earth excavation, embankment, concrete removal, furnishing and placing topsoil and seeding, existing track to be removed, existing topsoil to be stripped, clay cap and #10 turnouts. The quantities are presented in table F-1.

Quantities Generation

24. Earthwork volume quantities include earth excavation, embankment and clay cap. Track complete in place length was taken between the stations 69+60.81 and 97+59.19. Ballast and sub-ballast tonnage was calculated. Concrete removal was calculated by taking the area of the concrete to be removed at a depth of 1 foot. Furnishing and placing topsoil and seeding was determined from the length of the relocation and the ROW with an allowance for the track complete in place to be installed. Track to be removed is assumed to be two complete sets of track line and includes removal of all tracks material and ties while existing ballast material will remain. All removed material is to be stockpiled on site. All removed material remains the property of the railroad and is stored for railroad pickup. Topsoil to be stripped was determined from the length of the relocation and the ROW Clay cap was determined from the ROW to the cut-off wall.

REAL ESTATE

25. Total land required for the railroad relocation is 4.11 acres. The real estate required for the track relocation and CAP requirements temporary work limits is equal to the permanent easements for the relocated track. All land required for the project is owned by the Non-Federal Sponsor except for ROW easements owned by the railroads. Plate F-15 shows the real estate for the railroad relocation.

CONSTRUCTION SEQUENCE

26. The first feature of the project to be constructed is the relocated railroad track. The RCRA cap will be installed within the relocated R.R. ROW. The sub-ballast and ballast system will be installed and then the railroad track will be constructed. Topsoil and seeding is done to complete the relocation work. As the relocated railroad track is brought on line, the existing track shall be abandoned. After the existing line is abandoned, the ROW will be stripped and excavated.

ATTACHMENT 1

Design Criteria

Design criteria to be used for sidetracks with operating speeds no to exceed 15 mph are listed in the following table. The criteria are not intended for Yard and Terminal track, Intermodal track, Branch or Spur Lines, or any trackage with operating speed greater than 15 mph.

<u>CRITERIA</u>	<u>INDUSTRY TRACK</u>	<u>LEAD TRACK</u>	<u>LOAD / UNLOAD IN MOTION</u>
Turnout Size Note: turnouts in main tracks shall be No. 10 or larger	Number 8	Number 10	Number 10
Maximum Curves Degree Radius	12d-00'-00" 478.34'	10d-00'-00" 573.69'	10d-00'-00" 573.69'
Tangent Between Reverse Curves Preferred Minimum	100' 60'	100' 60'	100'
Maximum Grade Loop Track * Uncompensated ** Compensated at 0.04% per degree of curve	2.5% *	2.5% *	1.5% * 0.7% **
Vertical Curve Summits Sags Length	40 x algebraic differences in grades 50 x algebraic difference in grades 100' minimum	40 x algebraic differences in grades 50 x algebraic difference in grades 100' minimum	400 x algebraic differences in grades 500 x algebraic difference in grades 100' minimum

ATTACHMENT 2

Design Calculation and Assumptions

URS Greiner Woodward Clyde
CALCULATION COVER SHEET

Client: USACOE Project Name: CSX TRACK RELOCATION
Project/Calculation Number: 05-000.35477.19
Title: PRELIMINARY DESIGN CALCULATIONS AND QUANTITY TAKEOFF
Total Number of Pages (including cover sheet): _____ Total Number of Computer Runs: _____
Prepared By: MARK T. HEATON Date: _____
Checked By: DANIEL J. LOFTUS Date: _____

Description and Purpose:

DEVELOP AN ALIGNMENT FOR RAILROAD LEAD TRACK THAT
ADDRESSES CSXT COMMENTS AND MAXIMIZES SITE
REMBINDER FOR CDF CONSTRUCTION.

Design bases/references/assumptions:

- ① TOPO/CONTOURS AND PRELIM. ALIGNMENT BY COE.
- ② CSXT DESIGN STANDARDS AS PROVIDED BY RAILROAD
- ③ AREA: "MANUAL FOR RAILWAY ENGINEERING", 1996
- ④ COMPUTER GENERATED QUANTITY/DESIGN CALCULATIONS MADE HEREIN
USING MICROSTATION/GEOPAK.

Remarks/conclusions:

- ① HORIZONTAL ALIGNMENT MEETS BOTH GOALS OF DESCRIPTION.
- ② PRELIM. REVIEW OF ALIGNMENTS INDICATE MINOR MODIFICATIONS ARE
REQUIRED PRIOR TO CONSTRUCTION, BUT IS ACCEPTABLE (e.g. 200' V-C & 10° CURVES)
- ③ UTILITY CONFLICTS NOT SHOWN IN CALCULATIONS OR PLANS, PENDING
APPROVAL OF PRELIM. ALIGNMENTS.

Calculation Approved By: _____ Date: _____
Project Manager


Revision No.:	Description of Revision:	Approved By:
_____	_____	_____
_____	_____	_____
_____	_____	_____

Project Manager/Date

WVP Corporation
A Division of URS Greiner

01/08/99
Engineers-Architects-Planner
122 South Michigan Avenue
Suite 1970
Chicago, Illinois 60603
(312) 939-7704
Fax (312) 939-7372

Dan Loftus



CALCULATIONS TO DETERMINE
ALIGNMENT OF PROPOSED RR
RELOCATION WITH 100' TANGENT
BETWEEN REVERSING CURVES.
EXISTING (GIVEN) DATA TAKEN FROM
TO PO FILE (MICROSTATION).


PREPARED BY: DAN LOFTUS

DATE: 01/11/99


WVP Corporation
 A Division URS Greiner

Engineers-Architects-Planners
 122 South Michigan Avenue
 Suite 1970
 Chicago, Illinois 60603
 (312) 939-7704
 Fax (312) 939-7372

Jan Loftus




1089 1/4



WVP Corporation
A Division of URS Greiner

Engineers-Architects-Planners
122 South Michigan Avenue
Suite 1970
Chicago, Illinois 60603
(312) 939-7704
Fax (312) 939-7372

Dan Loftus




$$T = R_{\text{base}} \frac{1}{2} I$$

2079 04

WVP Corporation
A Division of URS Greiner

Engineers-Architects-Planners
122 South Michigan Avenue
Suite 1970
Chicago, Illinois 60603
(312) 939-7704
Fax (312) 939-7372

Dan Loftus




389 0/10

WVP Corporation

A Division of URS Greiner

Engineers-Architects-Planner
122 South Michigan Avenue
Suite 1970
Chicago, Illinois 60603
(312) 939-7704
Fax (312) 939-7372

Dan Loftus



$$T_1 + T_2 + 100 = \text{S.B.}(445.349)$$

I.

$$R \cdot C^{I/2} + T_2 + 100 = \text{S.I.}(445.549)$$


I.

4089

WVP Corporation
A Division of URS Greiner

Dan Loftus

Engineers-Architects-Planner
122 South Michigan Avenue
Suite 1970
Chicago, Illinois 60603
(312) 939-7704
Fax (312) 939-7372



589 0/10

WVP Corporation

A Division of URS Greiner

Dan Loftus

$$\theta = 151.698$$

$$28.302$$

$$\frac{151.698}{180} = 0.8428$$

$$I_1 + I_2 = 151.698$$

$$I_2 > I_1$$

IF $\overline{AB} \parallel \overline{EF}$
THEN $I_2 = I_1$
BUT THEY ARE
28.302° OFF
∴ 15.72% OFF
§ I_2 IS >
THAN I_1

$$\begin{aligned} \text{SO: } I_2 &= \frac{151.698}{2} \\ &= 75.849 \\ &\neq 1.157 \end{aligned}$$

$$\begin{aligned} I_1 &= 151.698 \\ &- 87.772 \\ \hline &63.926 \end{aligned}$$

$$T_1 = R \cdot I_2 = 358.784$$

$$T_2 = R \cdot I_2 = 553.064$$

WONG
MATH!



659

WVP Corporation
A Division of URS Greiner

Dan Loftus

Engineers-Architects-Planners
122 South Michigan Avenue
Suite 1970
Chicago, Illinois 60603
(312) 939-7704
Fax (312) 939-7372

$Q = 151.698$

151.698

$I_1 = \alpha$ if //
but 15.72%

$$\theta = I_1 + (180 - I_2)$$


$$I_1 = \frac{\theta}{2} (0.8428)$$

$$= 63.926^\circ$$

$$\therefore \alpha = 87.772$$

and

$$I_2 = 92.226$$



$$\overline{EF} = \overline{GF} = T_2 = R \sin I_2/2 = 597.806$$

$$\overline{BC} = \overline{CD} = T_1 = R \sin I_1/2 = 358.784$$


$$\overline{DE} \geq 100 \text{ (By definition)}$$

$$\therefore \overline{CF}_{\min} = 1056.59'$$

757 9 01

A Division of URS Greiner

Dan Loftus



8589


15.72% split
assumption 0%
N.G.

WVP Corporation

A Division of URS Greiner

Engineers • Architects • Planner
122 South Michigan Avenue
Suite 1970
Chicago, Illinois 60603
(312) 939-7704
Fax (312) 939-7372

Dan Loftus



$$\overline{CF} = T_1 + T_2 + 100$$
$$= (R \cdot I_1) + (R \cdot I_2) + 100$$

CONCLUSION:

AN ITERATIVE MATHEMATICAL SOLUTION
COULD BE MADE BY HAND, BUT GIVEN
THE NUMBER OF UNKNOWN'S A DIRECT
SOLUTION YIELDING A 100.00 FOOT
TANGENT (\overline{DE}) IS NOT POSSIBLE. FURTHER
CALCULATIONS WILL BE MADE USING
COMPUTER SPREADSHEET OR GEOPAK COGO.

9 27 9

011.

0500035477.19

DATE 1-18-99

FILE: 0535477.19\cwg0\align2d


CORO:

CALAIN1

308- COE-CSX

303#-05

070027-17h



URS Greiner Woodward Clyde

Job COE/CSX

Description Track Relocation Alignment

Project No. 05-00035477.19

Computed by MTH

Checked by

Page 1 of 3

Sheet of


Date 1-12-99

Date

Reference

TRIAL ERROR FOR CURVES #1 $\dot{E} = Z$ $R = 575'$

GIVEN: $\theta = 151.698$
 $\{ \overline{GH} = 939.319$
 measured in Microstation



$$\theta = I_1 + \frac{(180 - I_2)}{\alpha}$$

$$\overline{EF} = \overline{GF} = T_2 = R \tan \frac{I_2}{2}$$

$$\overline{BC} = \overline{CD} = T_1 = R \tan \frac{I_1}{2}$$

$\Delta DE = 100 =$ min tangent between the 2 curves
 (CSX standards) I_1 also will minimize
 the area for the combined disposal facility

① Try $\overline{I_2} = 95^\circ$

$$T_2 = 575 \tan \frac{95^\circ}{2} = 627.502$$

$$\alpha = 85^\circ$$

$$I_1 = \theta - 180 + I_2 = 166.698 = I_1$$

$$T_1 = 378.409$$

NO GOOD

$$\overline{DE} < 100$$

② Try $\overline{I_2} = 80.9$

$$T_2 = 482.482$$

$$\alpha = 100^\circ$$

$$I_1 = 51.698$$

$$T_1 = 278.573$$

NO GOOD

$$\overline{DE} > 100$$

③ Try $\overline{I_2} = 75^\circ$

$$T_2 = 575 \tan \frac{75^\circ}{2} = 441.213 = T_2$$

$$\alpha = 105^\circ$$

$$I_1 = 16.698$$

$$T_1 = 248.217$$

NO GOOD

$$\overline{DE} > 100$$

URS Greiner Woodward Clyde

Job COE/CSX

Project No. _____

Page _____ of _____

Description _____

Computed by MTH

Sheet _____ of _____

CURVES 1 & 2

Checked by _____

Date 1-14-96

Date _____

Reference

$$\text{TRY } I_2 = 79.5^\circ$$

$$T_2 = 478.222$$

$$\alpha = 100.5$$

$$I_1 = 51.198$$

$$T_1 = 275.481$$

No Good

$$DE > 100$$

$$\text{TRY } I_2 = 79.8$$

$$T_2 = 480.775$$

$$\alpha = 100.2$$

$$I_1 = 51.498$$

$$T_1 = 277.335$$

No Good

$$102.26\% = DE > 100$$

$$\text{TRY } I_2 = 80.5$$

$$T_2 = 486.723$$

$$\alpha = 99.5$$

$$I_1 = 52.198$$

$$T_1 = 281.677$$

No Good

$$DE < 100 \quad \text{by } 12.693$$

$$\text{TRY } I_2 = 79.9$$

$$T_2 = 481.628$$

$$\alpha = 100.1$$

$$I_1 = 51.538$$

$$T_1 = 277.953$$

Yes

$$DE = 100.118 \approx 100 \quad \text{GOOD}$$

URS Greiner Woodward Clyde

Job COE/CSX

Project No. _____

Page _____ of _____

Description HORIZONTAL ALIGNMENT

Computed by MTH

Sheet _____ of _____

FOR CURVES 3 & 4

Checked by _____

Date 1-11-89

Date _____

Reference

CONCLUSION:

IN ORDER TO MAXIMIZE THE AMOUNT OF SPACE AVAILABLE FOR THE CONFINED DISPOSAL FACILITY, A TRIAL & ERROR METHOD WAS USED TO DESIGN CURVES 3 & 4. THE SOLUTION THAT MAXIMIZES THE AREA IS ONE THAT HAS A 100' TANGENT BETWEEN THE TWO 575' (MIN RAD) CURVES (3 & 4). THIS WAS OBTAINED USING AN INFLUENCE ANGLE, $I_2 = 79.9^\circ$, FOR CURVE 4 & AN INFLUENCE ANGLE, $I_1 = 51.598^\circ$ FOR CURVE 3. THE TANGENT BETWEEN THE CURVES IS 100.118'.

URS Greiner Woodward Clyde

Job 06/CSX
Description HORIZONTAL ALIGNMENT
FOR CURVES 1&2

Project No. _____
Computed by MTH
Checked by _____

Page _____ of _____
Sheet _____ of _____
Date 1-13-99
Date _____

Reference

MODIFY ARC ANGLE (CURVES 1&2)

TRIAL 1

$$\alpha = 87.4879$$

$$I = 92.5121$$

$$\cancel{T = 575.101 I/2 = 600.180} \quad \text{NO GOOD}$$

$$\text{New } T = 602.0551$$

TRIAL 2

$$\alpha = 87.1627$$

$$I = 92.8373$$

$$I/2 = 46.419$$

NO

TRIAL #3

$$\alpha = 85.7978$$

$$I = 94.2022$$

$$I/2 = 47.1011$$

$$T = 618.798$$

TRIAL #4

$$\alpha = 85.4217$$

$$I = 94.5783$$

$$I/2 = 47.289$$

$$T = 622.885$$

$$R = \frac{T}{\tan I/2} = 565.009 \Rightarrow R = 400 \text{ same}$$

NO & GOOD

URS Greiner Woodward Clyde

Job COE/CSX
 Description HORIZ ALIGNMENT FOR
CURVES 18, 2

Project No. _____
 Computed by MTA
 Checked by _____

Page _____ of _____
 Sheet _____ of _____
 Date 1-13-89
 Date _____
 Reference _____

TRIAL #5

α 84.7255
 95 2745
 I/2 7.637
 Measured τ 619.724
 R $\tan^2 I/2$ 565 47 \rightarrow too S 11

NO GOOD

TRIAL #6

82.2926
 I 7.7074
 $I/2$ 48.8537
 Measured τ 618.6345
 R

NO GOOD

(New location for TURNOUT = 10)
TRIAL #7

α 291
 I 9 7087
 $\tan I/2$ 4447
 575 $\tan I/2$ 8 757
 Measured τ 6 1398
 R 610 80

τ α

TRIAL #8

URS Greiner Woodward Clyde

Job CGI/CSX

Project No. _____

Page _____ of _____

Description HORIZ. ALIGNMENT FOR

Computed by INTL

Sheet _____ of _____

CURVES 1 & 2

Checked by _____

Date 11-13-88

Date _____

Reference

** MUST USE TRIAL & ERROR METHOD GRAPHICALLY IN MICROSTATION IN ORDER TO GET CURVE #1 TO MEET the #10 TURNOUT*

CONCLUSION

THE SOLUTION FOR THE ALIGNMENT FOR CURVE 1 & 2 WAS OBTAINED GRAPHICALLY IN MICROSTATION BY MODIFYING THE ARC ANGLE OF CURVE 2 (GIVEN TO US BY COE) SO THAT A 575' RAD. CURVE #1 COULD MEET A #10 TURNOUT WHERE THE ELEVATION MATCHES BACK INTO EXISTING RAIL.

URS Greiner Woodward Clyde

Job COE/CSX

Project No. _____

Page _____ of _____

Description VERTICAL CURVE NOTES

Computed by MTH

Sheet _____ of _____

Date 1/18/90

Checked by _____


Date _____

Reference _____

CSX STANDARD SPEC.

115#

$$\begin{aligned} 31.625' &= 2.63542 \\ 23.625' &= 1.96457 \\ \hline &= 4.6000 \end{aligned}$$



$$\begin{aligned} 31.625'' \\ 23.625'' \\ \hline 8.000'' \end{aligned}$$

* Design Proposed vertical profile to be approx 8.000" above existing profile in order to minimize cuts & fills.

Copyright (1993) GEOPAK Corporation

All rights reserved

Project: coe-csx

Subject: alignment

Job No. 05 Operator: MH

Date: Wednesday January 20, 1999 11:07 am

SYSTEM FIX 4 ASEC 2 BEAR PRI 0 NOR NE STA 2 FILE: 'CHAIN'

G E O P A K

Is this latest &
most current print -
dit? Does not
attach data on
plans.
4/22/99

Describe Chain CHAIN1

Chain CHAIN1 contains:

1000 1005 CUR C1 CUR C2 CUR C3 CUR C4 1045

Beginning chain CHAIN1 description

Point 1000 N 1,513,722.6010 E 389,157.8190 Sta 68+10.81
Course from 1000 to 1005 N 0° 22' 26.48" E Dist 31.2507
Point 1005 N 1,513,753.8510 E 389,153.0230 Sta 68+42.06
Course from 1005 to PC C1 N 6° 00' 52.95" E Dist 85.7098

Curve Data

Curve C1

P.I. Station 75+54.21 N 1,514,462.0793 E 389,232.6434
Delta = 94° 54' 11.54" (RT)
Degree = 9° 57' 52.14"
Tangent = 626.4392
Length = 952.4147
Radius = 575.0000
External = 275.3241
Long Chord = 647.2124
Mid. Ord. = 186.1777
P.C. Station 69+27.77 N 1,513,839.0990 E 389, 7.0040
P.T. Station 78+80.19 N 1,514,343.4320 E 389, 7.7440
C.C. N 1,513,778.8395 E 389, 1.8363
Back = N 6° 00' 52.52" E
Ahead = S 79° 04' 55.94" E
Chord Bear = N 53° 27' 58.29" E

Curve Data

Curve C2

P.I. Station 81+57.71 N 1,514,290.8692 E 390,120.2438
Delta = 18° 25' 00.71" (RT)
Degree = 3° 20' 49.00"
Tangent = 277.5230
Length = 550.2588
Radius = 1,711.8826
External = 22.3495
Long Chord = 547.8930
Mid. Ord. = 22.0615
P.C. Station 78+80.19 N 1,514,343.4320 E 389,847.7440
P.T. Station 84+30.44 N 1,514,154.9080 E 390,362.1810
C.C. N 1,512,662.5344 E 389,523.5135
Back = S 79° 04' 56.03" E
Ahead = S 60° 39' 55.33" E
Chord Bear = S 69° 52' 25.68" E

Course from PT C2 to PC C3 S 60° 41' 51.80" E Dist 53.9599

Curve Data

Curve C3

P.I. Station	87+67.35	N	1,513,990.0186	E	390,655.9835
Delta	51° 35' 50.88"	(RT)			
At	9° 57' 52.14"				
Length	277.9502				
Radius	517.8138				
External	575.0000				
Long Chord	63.6559				
Mid. Ord.	500.4929				
P.C. Station	57.3112				
P.T. Station	84+89.40	N	1,514,126.0520	E	390,413.5970
P.C.	90+07.22	N	1,513,715.5670	E	390,699.9450
Back	N		1,513,624.6231	E	390,132.1825
Head	S 60° 41' 51.96"	E			
Chord Bear	S 9° 06' 01.08"	E			
	S 34° 53' 56.52"	E			

Course from PT C3 to PC C4 S 9° 06' 03.81" E Dist 100.1225

Curve Data


Curve C4

P.I. Station	95+88.97	N	1,513,141.1403	E	390,791.9591
Delta	79° 53' 59.74"	(LT)			
Angle	9° 57' 52.14"				
Tangent	481.6272				
Length	601.8472				
Radius	575.0000				
External	175.0558				
Long Chord	738.4361				
Mid. Ord.	134.2018				
P.C. Station	91+07.34	N	1,513,616.7080	E	390,715.7820
P.T. Station	99+09.19	N	1,513,132.7380	E	391,273.5130
Back	N		1,513,707.6505	E	391,283.5442
Head	S 9° 06' 01.67"	E			
Chord Bear	S 69° 00' 01.41"	E			
	S 49° 03' 01.54"	E			

Course from PT C4 to 1045 S 85° 59' 59.58" E Dist 90.8078


Point 1045 N 1,513,134.1530 E 391,364.3070 Sta 100+00.00

Adding chain CHAIN1 description



OLD PROFILE
EE NEXT PAGE
FOR N O PROFILE

NE 720



Job COE/CSX

Project No. _____

Sheet ____ of ____

Description DRAINAGE DITCH

Computed by MTM

Date 2-10-89

Checked by _____

Date _____

DRAINAGE DITCH ALONG PROPOSED ALIGNMENT

See COMMENT Reference
on plans regarding
drainage ditch(es)

DUE TO THE VERY FLAT TOPOGRAPHY OF THE ~~SITE~~ A DITCH WITH 3:1 SIDE SLOPES, 0.3% SLOPE GRADIENT & A 1 FOOT MINIMUM DEPTH WAS PROPOSED TO ROUTE WATER AWAY FROM THE PROPOSED RAILROAD ALIGNMENT. THE DITCH WAS PROPOSED TO RUN ALONG THE SOUTH SIDE OF THE PROPOSED ALIGNMENT, STARTING AT THE EAST END AND MATCHING EXISTING GROUND AT THE WEST END.

THIS DID NOT WORK DUE TO THE EXTREMELY FLAT TOPOGRAPHY. A DITCH WITH THIS MIN. SLOPE GRADIENT WOULD NOT MATCH EXISTING AT THE WEST END OF THE PROPOSED ALIGNMENT.

SOLUTION:

① RAISE THE PROPOSED PROFILE SO THAT THE TYPICAL SECTION IS AT OR ABOVE THE EXISTING GROUND LINE. THIS WOULD ALLOW THE SUB-BALLAST TO ACT AS THE SIDE SLOPE OF A NATURAL DITCH & THE WATER WOULD FLOW NATURALLY ALONG THE PROPOSED ALIGNMENT.

② USE A 3:1 SIDE SLOPE DITCH WITH A 2 FOOT DEPTH & NO SLOPE GRADIENT. THE DITCH WILL CATCH ANY RUNOFF SO THAT THE RAILROAD BED WILL NOT BE AFFECTED.

* SOLUTION ② WAS USED ALONG WITH RAISING THE PROFILE SO THAT THE ENTIRE TYP. SECT. IS ABOVE THE EXISTING GROUND LINE. ~~THIS~~ BECAUSE OF THE FLAT TOPOGRAPHY & THE SANDY SOILS (BORING LOGS) ~~THIS~~ WE DON'T EXPECT MUCH RUNOFF IN THE AREA OF THE PROPOSED ALIGNMENT, BUT THE DITCH IS A SAFEGUARD IN THE CASE THAT SOME RUNOFF OCCURS.

Table F - 1 Railroad Relocation Material Quantities

Item	Unit	Contractor	Railroad	Total Quantity
Track Complete in Place	LINEAR FEET	2,798	183	2,981
Ballast	TONS	1,628	104	1,732
Sub-Ballast	TONS	6,029	692	6,721
Earth Excavation	CUBIC YARDS	4,926	0	4,926
Embankment	CUBIC YARDS	0	0	0
Concrete Removal	SQUARE YARDS	476	0	476
Furnishing and Placing Topsoil and Seeding	SQUARE YARDS	15,260	0	15,260
Track to be Removed	LINEAR FEET	5,321	0	5,321
Topsoil to be Stripped	SQUARE YARDS	21,662	0	21,662
Clay Cap	CUBIC YARDS	18,720	0	18,720
#10 Turnout	EACH	Q	1	1
Silt Filter Fence	FOOT	4,080	0	4,080

URS Greiner Woodward Clyde

Job COE/CSX

Project No. _____

Page _____ of _____

Description PROFILE & CROSS SECTION CHANGED

Computed by MTH

Sheet _____ of _____

FOR BACKSHEK SUBMITAL PER 100% COMMENTS

Checked by _____

Date 5/17/99

Date _____

Reference _____

- PROFILE WAS RAISED ^{2'} TO ALLOW FOR A 2' RCRA CAP TO BE PLACED THROUGHOUT THE 60' R.R. EASEMENT. THE NEW QUANTITIES ARE SHOWN ON THE FOLLOWING PAGE

- CROSS SECTIONS WERE RECUT @ 5' IN ~~THE~~ BOTH THE VERTICAL & THE HORIZONTAL. TOPSOIL, STRIPPING, & RCRA CAP SHOWN IN ALL CROSS SECTIONS

THE DITCH WAS CHANGED FROM A 1' BOTTOM TO A 3' BOTTOM FOR CONSTRUCTABILITY

**COE/CSX TRANSPORTATION TRACK RELOCATION
AT THE INDIANA HARBOR CONFINED DISPOSAL FACILITY**

Project #: 0500035477.19
Computed by: MTH
July 14, 1999

SUMMARY OF QUANTITIES

ITEM	UNIT	TOTAL QUANTITIES	CONTRACTOR	RAILROAD
TRACK COMPLETE IN PLACE	L.F.	2981	2798	183
BALLAST	TONS	1732	1628	104
SUB-BALLAST	TONS	6721	6029	692
EARTH EXCAVATION	CU. YD.	4926	4926	0
EMBANKMENT	CU. YD.	0	0	0
CONCRETE REMOVAL	SQ. YD.	476	476	0
FURNISHING AND PLACING TOPSOIL AND SEEDING	SQ. YD.	15260	15260	0
TRACK TO BE REMOVED	L.F.	5321	5321	0
TOPSOIL STRIPPING	SQ. YD.	21662	21662	0
CLAY CAP	CU. YD.	18720	18720	0
#10 TURNOUT	EACH	1	0	1
SILT FILTER FENCE	FOOT	4080	4080	0

**COE/CSX TRANSPORTATION TRACK RELOCATION
AT THE INDIANA HARBOR CONFINED DISPOSAL FACILITY**

PROJECT #: 0500035477.19
DESCRIPTION: CUT AND FILL QUANTITIES
COMPUTED BY: MTH
DATE: May 21, 1999

AVG VOLUME (cy) = [D(A1+A2)/2]/27

A1=AREA1 (sf)

A2=AREA2 (sf)

D=DISTANCE BETWEEN AREAS

EE=EARTH EXCAVATION

FE=PROPOSED EMBANKMENT

SB=PROPOSED SUB-BALLAST

B=PROPOSED BALLAST

STA	EE (sf)	EMB (sf)	SB (sf)	B (sf)	VOL EE (cy)	VOL EMB (cy)	VOL SB (cy)	VOL B (cy)
6810.81	0.0	0.0	0.0	0.0				
6900	48.1	0.0	13.1	4.7	79.4	0.0	21.6	7.7
7000	60.0	0.0	22.0	7.7	200.1	0.0	0.0	22.9
7100	96.7	0.0	22.0	7.7	290.2	0.0	81.5	28.5
7200	7.3	0.0	23.1	7.7	192.6	0.0	83.5	28.5
7300	7.1	0.0	43.4	7.7	26.7	0.0	123.1	28.5
7400	6.9	0.0	60.5	7.7	26.0	0.0	192.4	28.5
7500	6.9	0.0	82.7	7.7	25.6	0.0	265.1	28.5
7600	7.0	0.0	86.0	7.7	25.7	0.0	312.3	28.5
7700	7.0	0.0	82.9	7.7	25.9	0.0	312.8	28.5
7800	6.5	0.0	76.7	7.7	25.0	0.0	295.6	28.5
7900	6.7	0.0	76.1	7.7	24.4	0.0	283.0	28.5
8000	7.7	0.0	73.8	7.7	26.7	0.0	277.6	28.5
8100	6.7	0.0	56.9	7.7	26.7	0.0	242.0	28.5
8200	6.7	0.0	55.2	7.7	24.8	0.0	209.4	28.5
8300	7.1	0.0	55.4	7.7	25.6	0.0	208.5	28.5
8400	6.9	0.0	46.8	7.7	25.9	0.0	191.1	28.5
8500	7.0	0.0	48.9	7.7	25.7	0.0	177.2	28.5
8600	7.0	0.0	51.0	7.7	25.9	0.0	185.0	28.5
8700	7.6	0.0	50.0	7.7	27.0	0.0	187.0	28.5
8800	6.8	0.0	57.1	7.7	26.7	0.0	198.3	28.5
8900	7.2	0.0	48.8	7.7	25.9	0.0	196.1	28.5
9000	6.6	0.0	45.7	7.7	25.6	0.0	175.0	28.5
9100	6.9	0.0	48.8	7.7	25.0	0.0	175.0	28.5
9200	7.3	0.0	52.9	7.7	26.3	0.0	188.3	28.5
9300	5.8	0.0	52.2	7.7	24.3	0.0	213.1	28.5
9400	6.1	0.0	42.0	7.7	22.0	0.0	193.0	28.5
9500	138.9	0.0	67.9	7.7	268.5	0.0	203.5	28.5
9600	147.7	0.0	37.3	7.7	530.8	0.0	194.8	28.5
9700	190.8	0.0	22.0	7.7	626.9	0.0	109.8	28.5
9800	224.2	0.0	22.0	7.7	768.4	0.0	81.5	28.5
9909.19	0.0	0.0	0.0	0.0	453.2	0.0	44.5	15.5

3973.6 0.0 5521.9 844.6


TOTAL EARTH EXCAVATION: 3974 cy
TOTAL EMBANKMENT: 0 cy
TOTAL SUB-BALLAST: 5522 cy
TOTAL BALLAST: 845 cy

RA 572 22

EC

E FOR B

RO



TASK	WEEK														
	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
Track Removal															
Topsoil Stripping															
Earth Excavation															
Subbase Preparation															
Clay Fill Placement															
Sub-ballast / Ballast Placement															
Rail / Tie Placement															
Final Grading															
Landscaping															
Project Closeout															

Prepared By:

URS Greiner Woodward Clyde



US Army Corps of Engineers
CSXT Track Relocation at the
Indiana Harbor CDF

Construction Sequence Schedule

ATTACHMENT 3

Local Sponsor's Concurrence with Preliminary Railroad Relocation Design



VICE-PRESIDENT
EDUARDO MALDONADO

PRESIDENT
FRANK KOLLINTZAS

EXECUTIVE DIRECTOR
ADRIANE ESPARZA

ROBERT A. PASTRICK MARINA
3301 ALDIS AVENUE
EAST CHICAGO, IN
46312

June 10, 1999


Sterling Johnson, ED-DC
US Army Corps of Engineers
111 N. Canal Street, Suite 600
Chicago, IL 60606

Re: CSX Transportation Track Relocation at the Indiana Harbor Confined Disposal
Facility


Dear Mr. Johnson:

The East Chicago Waterway Management District has reviewed the final design memorandum for the above project and has no additional comments.

Sincerely,


Adriane Esparza

AE/ae



GENERAL NOTES

1. ALL WORK ASSOCIATED WITH THE TRACK TO BE REMOVED SHALL BE COORDINATED WITH THE MAINTENANCE. ALL EXISTING MATERIALS (RAIL, TIES, SPICES, PLATES, ETC.) SHALL REMAIN THE PROPERTY OF THE MAINTENANCE AND SHALL BE STORED BY THE CONTRACTOR AFTER REMOVAL FOR PICKUP BY THE MAINTENANCE. EXISTING BALLAST AND SUBBALLAST SHALL BE MAINTAINED IN PLACE.

2. ALL ITEMS SHOWN FOR REMOVAL SHALL BECOME THE PROPERTY OF THE CONTRACTOR, UNLESS TIES BY THE OWNER FOR THEIR SALVAGE PURPOSES. EACH ITEM SO TIESD SHALL BE FULLY DISINTEGRATED AND STORED BY THE CONTRACTOR FOR OWNER PICKUP.

3. MAINTENANCE FORCES WILL COMPLETE ALL MAINT AND ASSOCIATED TRACK WORK WITHIN THE FOLLOWING LIMITS:
STATION 10+00 TO STATION 10+100

STATION 10+100 TO STATION 10+150

THE CONTRACTOR SHALL, HOWEVER, BE RESPONSIBLE FOR ALL WORKING OPERATIONS, INCLUDING MATERIALS AND LABOR, WITHIN THE ABOVE-MENTIONED LIMITS.

4. THE LOCATIONS OF THOSE BURIED AND MOVED OVERHEAD UTILITIES ARE APPROXIMATE, ARE SHOWN FOR CONTRACTOR INFORMATIONAL USE ONLY AND ARE NOT TO BE REFERENCED FOR CONSTRUCTION PURPOSES. THE IMPLIED PRESENCE OR ABSENCE OF UTILITIES IS NOT TO BE CONSIDERED BY THE ENGINEER, CONTRACTOR OR SUBCONTRACTOR TO BE AN ACCURATE AND COMPLETE REPRESENTATION OF UTILITIES THAT MAY OR MAY NOT EXIST ON THE CONSTRUCTION SITE. BURIED AND MOVED OVERHEAD UTILITY LOCATION IDENTIFICATION AND MARKING ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. REMOVAL, DISCONNECTION, PROTECTION, ETC. OF ANY SUCH UTILITY MUST BE COORDINATED BETWEEN THE CONTRACTOR, UTILITY COMPANY OR OWNER, SITE SAFETY, INCLUDING THE ASSIGNMENT OF PERSONNEL ASSOCIATED WITH BURIED AND MOVED OVERHEAD UTILITIES, REMAIN THE SOLE RESPONSIBILITY OF THE CONTRACTOR.

5. THE CONTRACTOR'S ATTENTION IS DIRECTED TO THE FACT THAT THERE EXISTS WITHIN THE STATE OF ILLINOIS A "JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION" SYSTEM. SOME UTILITIES THAT ARE FOUND ON SITE MAY BE A PART OF THIS SYSTEM. THIS SERVICE CAN BE REACHED AT 800-362-5544.

6. A QUANTITY OF SALT FILTER FENCE HAS BEEN INCLUDED IN THE CONTRACT. ACTUAL LOCATION AND QUANTITY OF SALT FILTER FENCE WILL BE AS DIRECTED BY THE REQUIREMENTS, THE ENGINEER OR OWNER. TYPICALLY, THE PLACEMENT OF SALT FILTER FENCE WILL BE REQUIRED PARALLEL TO THE CONSTRUCTION WORK ZONE PLACED 1-FOOT INSIDE THE PROJECT LIMITS.

7. THE CONTRACTOR SHALL COORDINATE ALL TRACK AND/OR ROADWAY CLOSURES WITH THE OWNER'S EMT AND STATE OF ILLINOIS TWO WEEKS NOTICE SHALL BE PROVIDED PRIOR TO ANY CLOSURES.

8. FOR DETAILS OF TRACK PLACEMENT SEE DETAILED DRAWINGS IN THE SPECIFICATIONS.

9. CONTRACTOR WORK LIMITS ARE DEFINED BY THE FOLLOWING:

1. FOR TRACK REMOVAL, EXISTING TRACK EASEMENT AS SHOWN IN PLANS.

2. FOR NEW TRACK, PROPOSED 50-FOOT EASEMENT PLUS 5 FEET ON EACH SIDE AS SHOWN IN PLANS.

ALL STORAGE OF MATERIAL SHALL BE WITHIN THESE LIMITS.

10. IN ACCORDANCE TO THE SITE SHALL BE MAINTAINED FROM ILLINOIS STATE HIGHWAY 101 AT THE LOCATION SHOWN IN PLANS, UNLESS APPROVED BY THE ENGINEER.



NO.	REVISION	DATE	BY	CHKD.	APP'D.
1					
2					
3					
4					
5					
6					
7					
8					
9					
10					

DESIGNER	CHECKED	IN CHARGE	DATE
U.S. ARMY ENGINEER DISTRICT CORPS OF ENGINEERS CHICAGO, ILLINOIS			
LARS G. GRIFFIN, AIA			

PROJECT	DATE
CSX TRANSPORTATION TRACK RELOCATION AT THE KOSKUSKUS HARBOR CONCRETE DISPOSAL FACILITY TYPE 2, 2.5, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100	

SHEET	REFERENCE
2	

PROPOSED CURVE DATA

CURVE NO. 1
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 2
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 3
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 4
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 5
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 6
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 7
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 8
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 9
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 10
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88

PROPOSED CURVE DATA

CURVE NO. 1
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 2
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 3
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 4
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 5
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 6
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 7
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 8
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 9
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 10
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88

PROPOSED CURVE DATA



CURVE NO. 1
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 2
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 3
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 4
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 5
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 6
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 7
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 8
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 9
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 10
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88

PROPOSED CURVE DATA

CURVE NO. 1
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 2
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 3
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 4
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 5
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 6
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 7
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 8
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 9
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 10
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88

PROPOSED CURVE DATA

CURVE NO. 1
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 2
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 3
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 4
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 5
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 6
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 7
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 8
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 9
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88
CURVE NO. 10
P.C. 151442.88 P.T. 151442.88 C.P. 151442.88




U.S. Army Corps of Engineers
Chicago District



DATE	1/1/88
BY	URS
CHECKED BY	URS
APPROVED BY	URS
REVISION	

U.S. ARMY ENGINEER DISTRICT
CORPS OF ENGINEERS
CHICAGO, ILLINOIS
URS CREINER WOODWARD
A Division of URS Consultants

CSX TRANSPORTATION
TRACK RELOCATION AT THE
INDIANA HARBOR
CONFINED DISPOSAL FACILITY
SITE PLAN

SHEET
NUMBER
3
OF 4





MATCHLINE
SEE SHEET 4

MATCHLINE
SEE SHEET 1


LIMITS OF EXISTING TRACKS TO BE REMOVED

U.S. Army Corps
of Engineers
Chicago District


DESIGNED BY: GARY J. WILSON
CHECKED BY: JAMES P. WILSON
U.S. ARMY ENGINEER DISTRICT
CORPS OF ENGINEERS
CHICAGO, ILLINOIS
LRS GREINER WOODWARD
CONSULTING ENGINEERS

CSX TRANSPORTATION
TRACK RELOCATION AT THE
MADISON AVENUE
CONCRETE DEPOT FACILITY
PLAN AND PROFILE

SHEET
REFERENCE
NUMBER
5



<p>U.S. Army Corps of Engineers Chicago District</p>	
<p>DESIGNED BY DATE: 7/9/98 DRAWN BY: SCALE: P. 50 CHECKED BY: DRAWING CODE: 000 DESIGNED BY: 000 CHECKED BY: 000</p>	
<p>U.S. ARMY ENGINEER DISTRICT CORPS OF ENGINEERS CHICAGO, ILLINOIS</p>	
<p>URS GREINER WOODWARD A Division of URS Corporation</p>	
<p>CSX TRANSPORTATION TRACAP FACILITY INDIANA HARBOR CONFINED DISPOSAL FACILITY</p>	
<p>PLAN AND PROFILE</p>	
<p>SHEET REFERENCE NUMBER 7</p>	



10
SHEET
REFERENCE
NUMBER

CSX TRANSPORTATION
TRACK RELOCATION AT THE
INDIANA HARBOR
CONFIRMED DISPOSAL FACILITY
CROSS SECTIONS
STATION 77+00 TO 81+00

U.S. ARMY ENGINEER DISTRICT
CORPS OF ENGINEERS
CHICAGO, ILLINOIS


URS GREINER WOODWARD CLPDC


A Division of URS Corporation


DESIGNED BY: LMC
DATE: 7/16/99
DRAWN BY: LMC
SCALE: P-10
CHECKED BY: LMC
DATE: 7/16/99
REVIEWED BY: LMC
DATE: 7/16/99

NO.	REVISION	DATE	BY	CHKD.
1	ISSUED FOR CONSTRUCTION	7/16/99	LMC	LMC
2	ISSUED FOR CONSTRUCTION	7/16/99	LMC	LMC
3	ISSUED FOR CONSTRUCTION	7/16/99	LMC	LMC
4	ISSUED FOR CONSTRUCTION	7/16/99	LMC	LMC
5	ISSUED FOR CONSTRUCTION	7/16/99	LMC	LMC
6	ISSUED FOR CONSTRUCTION	7/16/99	LMC	LMC
7	ISSUED FOR CONSTRUCTION	7/16/99	LMC	LMC
8	ISSUED FOR CONSTRUCTION	7/16/99	LMC	LMC
9	ISSUED FOR CONSTRUCTION	7/16/99	LMC	LMC
10	ISSUED FOR CONSTRUCTION	7/16/99	LMC	LMC

U.S. ARMY ENGINEER DISTRICT
CORPS OF ENGINEERS
CHICAGO, ILLINOIS








PARCEL 1:

That part of the South half (50%) of the Southwest Quarter (320) of Section Seventeen (17), Township Thirty-Seven (37) North, Range Nine (9) East of the Second Principal Meridian, lying East of the right-of-way of the Chicago and Calumet Traction Railroad, conveyed by deed dated January 3, 1896, and recorded in the Recorder's Office of Lake County, Indiana, June 25, 1896, in Book 44, page 104, excepting therefrom the following interests, to-wit:

That part thereof conveyed by deed dated July 26, 1896, to the Indiana Pipe Line Company, a corporation of Indiana, which deed was recorded December 6, 1896, in the Recorder's Office of Lake County, Indiana, in Book 46, pages 175 and 176; that part thereof conveyed by deed dated July 6, 1896, to the East Chicago Sanitary District, a corporation of Indiana, and deed being recorded August 1896, in the Recorder's Office of Lake County, Indiana, in Book 52, page 25, is included; that part thereof conveyed by deed dated July 22, 1896, to the Western Indiana Railway Company, a corporation of Indiana, and deed being recorded in said Recorder's Office on October 27, 1896, in Book 75, pages 304 to 306, inclusive; and that part thereof conveyed by the Company to South Chicago and Southern Railroad Company by deed dated September 11, 1897, and recorded October 6, 1902, in Book Record 26, page 705, and that part thereof conveyed to WACC Oil Company, a corporation of Indiana, by deed dated March 26, 1904, in Document No. 150433 and conveyed to the State of Indiana by Trustee's deed recorded April 1, 1904, in Document No. 150434.

PARCEL 2:

The Northwest Quarter (360) and the North half (180) of the Southwest Quarter (320) of Section Twenty (20), Township Thirty-Seven (37) North, Range Nine (9) East of the Second Principal Meridian, in the City of East Chicago, Lake County, Indiana EXCEPTING THEREFROM a Grant to the United States of America, recorded April 15, 1895, in Miscellaneous Record 44, page 472, for a two hundred (200) foot canal, and also EXCEPTING the present right-of-way of the Chicago and Calumet Traction Railway Company, and the South Chicago and Southern Railway Company.



CURVE	DELTA	RADIUS	ARC	CHORD BEARING & DISTANCE
C-1	32°05'11"	2804.70'	1568.99'	S 73°13'30" E - 1550.21'
C-2	50°18'22"	573.70'	563.82'	N 29°13'45" W - 560.28'
C-3	92°53'21"	573.70'	918.40'	N 65°27'42" E - 811.44'
C-4	71°47'45"	573.70'	719.68'	S 31°51'54" W - 872.78'
C-5	67°40'09"	573.70'	617.51'	S 33°51'19" W - 838.81'
C-6	89°08'58"	573.70'	892.65'	S 44°35'46" E - 809.23'

LEGEND

- GOV'T CORNERS W/PHYSICAL MONUMENT
- GOV'T CORNERS W/NO MONUMENT ESTABLISHED
- FENCE
- RAILROAD
- BOUNDARY LINE
- - - SECTION LINE

E.C.I. REFINERY SITE	
URS GREINER WOODWARD CLYDE	
DATE	DATE
BY	BY
SECTION 20 T-37-N. R-9-W	
SCALE 1" = 40'	AND REVISIONS